APOLLO NZ GLOBAL

GLOBAL PROJECT SUPPLY / INDIA



INDIA TECHNICAL RESOURCE SERIES / 02

Sports Facilities

Cricket academy and multi-sport hall project guide

01 / HOW TO USE THIS GUIDE

A better tender starts with a better brief.

This pack gives project teams a practical starting structure before a product model, pricing or procurement commitment is established. Use it with current drawings and your appointed Indian professionals.

01

Confirm the application

Identify the users, expected operating conditions, site, city/state and capacity before selecting products.

02

Select a product pathway

Compare relevant systems using actual intended use, interfaces and available model-specific evidence.

03

Separate local works

Show engineering, civil works, electrical connections, permits, installation and acceptance outside Apollo supply.

04

Issue an RFQ-ready schedule

Record quantities and required documents only when supported by the project brief; use Apollo's online unpriced BOQ centre.

KEY PRINCIPLE

Technical resource only. Not an approved specification, installed-price quotation or certification of compliance.

02 / KEY TECHNICAL DECISIONS

Design the use, not just the court.

Four early decisions that have the largest effect on product fit, project packaging and avoidable variation.

01

State the training programme

Primary sports, coaching capacity, lane/court counts, indoor/outdoor use and competition or federation evidence requests.

02

Check the usable volume

Cricket net containment, run-ups, halls' court/run-off clearances and height, spectators and safe circulation require scaled layouts.

03

Coordinate equipment packages

Practice netting, flooring, equipment, lighting, seating, video and scoring should each have a clear technical and local installation interface.

04

Plan long-term operation

Sports surface care, net replacement, storage and deployment, consumables, spare parts, network and power maintenance.

CONCEPT / PRACTICE LANE & SAFE CIRCULATION

INDICATIVE ONLY / NOT TO SCALE



03 / UNPRICED SCOPE FRAMEWORK

Equipment and responsibilities.

Use this matrix to start the bill of quantities. Product supply and local project work must be distinguished before quotations or tender submissions.

#	Item / system	Review owner	Required evidence
01	**Cricket practice netting and ball containment**	APOLLO SUPPLY REVIEW	Netting material and current product data
02	**Net support structure, tracks or suspensions**	APOLLO SUPPLY REVIEW	Selected-system layout and component information
03	**Lane separators, access and protection**	APOLLO SUPPLY REVIEW	Layout and component information
04	**Practice pitch/strip surfacing**	APOLLO SUPPLY REVIEW	Available surface technical and maintenance guide
05	**Run-up / auxiliary training surfaces**	APOLLO SUPPLY REVIEW	Compatible surface details
06	**Training-zone lighting**	APOLLO SUPPLY REVIEW	Selected fitting photometric/electrical information where available
07	**Bowling and performance training equipment**	APOLLO SUPPLY REVIEW	Model-specific equipment sheets
08	**Groundworks, footings and drainage**	INDIAN LOCAL TEAM	Local site survey, ground/design information

PROJECT-SPECIFIC QUANTITIES

Leave line-item quantities blank until dimensions and drawings are confirmed. The online Tender Centre can generate a fuller, editable CSV with selected optional equipment.

04 / DOCUMENT REGISTER

Documents worth requesting.

Evidence must be current, applicable to the proposed model and independently reviewed where required. A document checklist is not a claim of existing certification.

FROM THE PROJECT TEAM

01 Site plan, photos and available dimensions

02 Lane count and coaching/sport programme

03 Existing slab/ground and drainage notes

04 Local support or foundation drawings where available

05 Tender/BOQ document and delivery schedule if applicable

FROM THE PRODUCT REVIEW

01 Netting/frame component data for the chosen system

02 Current installation and fixing requirements

03 Surface and equipment information where selected

04 Packing, spares and maintenance instructions

RESPONSIBILITY CHECK / BEFORE FINAL RFQ

Sports project architect	Sport programme, usable clearances, safe player flow, accessibility and venue occupancy/egress.
Apollo product review	Equipment families, current product build-up, component schedule, sport performance evidence where genuinely available.
Local civil/electrical team	Base, slab, foundations, drainage, mountings, power, assembly, commissioning and testing.

Do not claim approval, compliance, certification or guaranteed performance without evidence for the exact selected item and project.

05 / TENDER TO QUOTATION

The pathway to an actionable RFQ.

Use the India Specification & Tender Centre to select equipment lines, add project context and prepare an unpriced downloadable schedule before requesting a confirmed supply quotation.

01

Prepare the site brief

Send city/state, project programme, use, dimensions, site drawings and the appointed professional team's requirements.

02

Build the unpriced schedule

Select the relevant cricket, sports hall or architectural louvre module; distinguish product supply from local works.

03

Request an Apollo review

Submit the existing enquiry form. Apollo evaluates feasible products and current technical evidence and confirms a specific supply scope.

04

Attach project documents

After the enquiry reference is issued, use the secure project upload service to submit drawings, BOQ/RFP documents and photographs.

START YOUR PROJECT BRIEF

Open India Tender Centre / Cricket academy

https://apollonzglobal.com/global-projects/india/specification-tender-centre?module=cricket

Apollo NZ Global | supply only | sales@apollonzglobal.com